BANGALORE DIVISION.

FORM OF ADVERTISEMENT.

Notice dated 3rd September 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 19th September 1927, for restoring the Panditha Agrahara Tank of Hosakote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 to 5.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of rupees three hundred in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Panditha Agrahara Tank in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract for Pandithana Agrahara Tank.

No.	Items of work	Unit	Per.
	Bund.		
1	Clearing jungle with thick prickly pear	18	Grade
2	Cutting grips	412	C.yd.
3	Earthwork to bund with watering and tamping ...	3,888	,,
4	Turfing	3,707	S.yd.
5	New stone work	1,180	C.yd.
6	Old stone work	154	,,
7	New grade stone including cutting figures and painting ...	21	Each
8	New index stones including cutting figures and painting. ...	21	,,
9	New registered number stone including cutting figures and painting.	1	,,
10	New burnt metal stones including cutting figures and painting.	2	,,
11	New date stone	1	,,
12	New grade stone	1	,,
	Waste Weir 215' long.		
13	Earthwork excavation earth to be used to flank bund ...	465	C.yd.
14	Concrete in surki mortar	544	C.ft.
15	Burnt brick in surki mortar	871	,,
16	Plastering with surki mortar	13·02	Sqr.
17	New stone work	302	C.yd.
18	Old stone work	100	,,
19	Burnt stone slabs 6"	261	S.ft.

R. W. SCALDWELL,
Executive Engineer.

6 I